

Appendix F – Long Term Pollution Prevention **Plan**

Long Term Pollution Prevention Plan

This plan was developed in compliance with the Massachusetts Department of Environmental Protection Stormwater requirements.

Good Housekeeping

The proposed site is designed to maintain high water quality treatment for all runoff. A general maintenance plan has been prepared and will be followed in a strict and complete manner as required.

Spill Prevention Plan

No hazardous materials are will be stored on site. However the following spill prevention plan will be incorporated into the Long Term Pollution Prevention Plan:

- Manufacturers' recommended methods for spill cleanup will be clearly posted and site personnel will be made aware of the procedures and the location of the information and cleanup supplies.
- Materials and equipment necessary for spill cleanup will be kept in the on-site material storage area. Equipment and materials will include, but is not limited to, brooms, dust pans, mops, rags, gloves, goggles, kitty litter, sand, sawdust and plastic and metal trash containers specifically for this purpose.
- All spills will be cleaned up immediately after discovery.
- The spill area will be kept well ventilated and personnel will wear appropriate protective clothing to prevent injury from contact with a hazardous substance.
- Spills of toxic or hazardous material will be reported, regardless of size, to the Massachusetts Department of Environmental Protection at 888-304-1133.
- Should a spill occur, the spill prevention plan will be adjusted to include measures to prevent another spill and to cleanup up the spill should another occur. A description of the spill, along with the causes and cleanup measures will be included in the updated spill prevention plan.
- The construction superintendent responsible for daily operation on the construction site will be the spill prevention and cleanup coordinator. The superintendent will designate at least three site personnel to receive spill prevention cleanup and training. These individuals will each become responsible for a particular phase of prevention and cleanup. The names of responsible spill personnel will be posted in the material storage area and in the on-site job trailer.

Stormwater BMP Maintenance

A full stormwater operation and maintenance plan has been prepared (see Appendix D of this report) in order to ensure that the system will function properly throughout the year.

Landscape and Lawn Maintenance

Routine mowing and associated maintenance of all landscape features will occur weekly or as needed to prevent excessive growth and debris from occurring on site.

Solid Waste Management

Solid waste is handled on site and will comply with all requirements on a local, state, and federal level.

Parking/Road Area Maintenance

Street sweeping shall occur 2-4 times per year. A snow management plan has been prepared (see Appendix D) to prevent dirty snow and salt from entering the resource area.

Training of Staff

All personnel on site will be well briefed on all requirements for implementing the Long Term Pollution Prevention Plan.

Emergency Contact for Implementing Long Term Pollution Prevention Plan

Tofino Associates, Inc.
31 Campus Plaza Rd
Hadley, MA 01035
413 256 0321